BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the work:- Patching pot holes in main and cross roads of Kodigehalli, tatanagara, Bhadrappa layout, devinagara, lottegollahalli, muneshwaranagara and surroundings areas in ward no. 8

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	167.74	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	Cum	86.92	
2	82.38	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification	Cum	1768.08	
3	406.55	Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification	Sqm	302.10	
4	313.00	Lead and disposal of Item No.1 & Road side debris	Cum	106.00	

No of corrections - Nil

"DTS Approved"

06.02

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

06/02

08.03.17